International Journal of Recent Development in Engineering and Technology
Website: www.ijrdet.com (ISSN 2347-6435 (Online) Volume 15, Issue 10, October 2026)

Design for Disassembly and Reversible Buildings: Principles, Strategies and Case Studies

Misreena R. M.[1], Anurudh R.[2]
[1]B.Tech Student, [2]Assistant Professor, Department of Civil Engineering, Ahalia School of Engineering and Technology, Palakkad, Kerala, India

***Abstract*—Buildings are generally designed to provide strength, safety and long service life, but conventional construction methods can make later adaptation and dismantling difficult. Permanent joints often damage connected materials during renovation or demolition, limiting opportunities for component reuse and increasing construction and demolition waste. Design for Disassembly (DfD) addresses this issue by considering the future removal, replacement and recovery of building components at the design stage. This paper presents the conceptual background of DfD and its relationship with the circular economy and the waste hierarchy, the key design principles, the main families of reversible connection systems, material-specific considerations, the layered view of buildings, the stages of a planned disassembly process, and the role of documentation, material passports and digital tools. Practical challenges, risk areas, economic and environmental considerations, and potential applications are discussed, and a conceptual design checklist is proposed. Two examples are examined: a redesigned apartment block in Helsinki, Finland, and The Container pavilion created for the Kochi-Muziris Biennale 2023. The examples illustrate how modular dimensions, accessible connections, independent building systems and recoverable materials can support adaptability and reuse. The paper is a qualitative review based on the seminar report and presentation supplied for this study and does not present new experimental measurements. The discussion indicates that DfD can support circular construction and material recovery, although its success depends on careful planning, suitable components, skilled work, supportive regulation and future demand for recovered materials.**

***Keywords*—adaptability, building layers, circular economy, construction waste, Design for Disassembly, material passports, material reuse, prefabrication, reversible buildings, reversible connections.**

I. Introduction

The building sector is one of the largest consumers of natural resources and one of the largest generators of solid waste. A single building brings together a wide range of materials and components, including structural frames, façades, services, partitions and finishes. These elements do not have identical service lives, and their functions may change as user needs, technologies and regulations develop.

A structural frame may remain serviceable for a century, whereas a mechanical system may need replacement after a few decades and an interior fit-out after only a few years. When all of these elements are tied together into a single, inseparable assembly, the shortest-lived part of the building effectively dictates how much disturbance the longer-lived parts must endure.

In conventional construction, components are often joined permanently or arranged so that one element cannot be removed without disturbing others. Cast-in services, welded connections, bonded finishes and wet joints are common examples. Renovation and end-of-life demolition may therefore damage materials that could otherwise remain useful. Demolition then becomes the default end of a building's life, and the materials leaving the site are frequently mixed, contaminated or physically damaged, which restricts them to low-value recycling or disposal.

Design for Disassembly (DfD) is an approach in which a building is planned so that its components can be separated and removed with minimal damage. Reversible buildings extend this idea by allowing elements to be repaired, replaced, rearranged or reused without major demolition. These approaches are closely related to the circular economy, which seeks to keep materials and products in use for as long as practicable rather than treating demolition waste as the inevitable end point. In this sense DfD is not a single technique but a design attitude: every joint, every layer and every document produced during design is judged partly by how it will behave when the building is eventually changed or taken apart.

This paper organises the concepts presented in the supplied seminar materials into an extended journal-style review. Section II describes the review approach and scope. Section III places DfD within the wider context of the circular economy and the waste hierarchy. Section IV sets out the principles of DfD, and Section V examines reversible connections and construction strategies, including material-specific, structural and durability considerations. Section VI discusses building layers and service life, Section VII describes the disassembly process, and Section VIII considers documentation, material passports and digital tools.

International Journal of Recent Development in Engineering and Technology
Website: www.ijrdet.com (ISSN 2347-6435 (Online) Volume 15, Issue 10, October 2026)

Section IX examines stakeholder roles and lifecycle integration. Section X discusses applications, benefits, challenges and limitations, and Section XI considers standards, policy and regional context. Section XII presents an implementation roadmap and a conceptual checklist. Section XIII examines two illustrative case studies, Section XIV offers a discussion and future scope, and Section XV concludes the paper.

II. Review Approach And Scope

This paper is a descriptive, qualitative review based on two supplied sources: the seminar report and the accompanying presentation on Design for Disassembly and Reversible Buildings. The materials discuss DfD principles, connection types, building layers, applications and two case studies. References listed in those materials are retained for further reading. The present paper elaborates the material of the seminar by explaining the reasoning behind each principle, by organising the content into a more complete framework, and by adding general engineering discussion that is consistent with widely accepted knowledge in the field.

Three limitations should be stated clearly. First, no independent field survey, structural testing, life-cycle calculation or verification of the cited publications was undertaken for this paper; reported project outcomes are presented as described in the supplied materials. Second, the case studies are illustrative rather than statistically representative, and conclusions drawn from two projects cannot be generalised to all building types, climates or regulatory environments. Third, where this paper proposes a conceptual framework, such as the checklist in Section X, it is offered as a structured aid to thinking and has not been validated against measured project data.




Figure 1: Design for disassembly: circular timber architecture

III. Background: Circular Economy And The Waste Hierarchy

A. From a Linear to a Circular Model

The traditional construction economy follows a linear pattern of extraction, manufacture, use and disposal. Raw materials are extracted, converted into products, assembled into buildings and, at the end of the building's life, discarded as demolition waste.

International Journal of Recent Development in Engineering and Technology
Website: www.ijrdet.com (ISSN 2347-6435 (Online) Volume 15, Issue 10, October 2026)

The circular economy replaces this pattern with closed or extended loops in which products and materials are maintained, shared, repaired, reused, remanufactured and, only as a last step, recycled. The aim is to retain the value that has already been invested in materials, including the energy and emissions embodied in their production, for as long as possible.

For buildings, this idea has a specific consequence. A building can only act as a store of reusable materials if those materials can be taken out again in a usable condition. A concrete beam cast monolithically into a slab, or a brick wall bonded with strong cement mortar, can usually be removed only by breaking it, after which it is rubble. By contrast, a steel beam bolted to a column, or a timber panel screwed to a frame, can be unfastened and lifted away intact. DfD is therefore the design-stage enabler of circularity in the built environment: it determines whether the building will later behave as a waste stream or as a material bank.

Figure 2 contrasts the two models. In the linear model every building ends in demolition and disposal. In the circular model the building is designed from the outset to pass through repeated phases of use, adaptation and disassembly, and the recovered components feed the next round of construction. The difference lies less in the materials themselves than in the way the building is put together and documented. The concept of a circular economy has been widely promoted in industry policy literature [11], and DfD can be seen as its translation into building design.




Figure 2: Linear versus circular building life cycle (schematic)

B. The Waste Hierarchy Applied to Buildings

The waste hierarchy ranks end-of-life options according to the value they preserve. Reuse of a component in its existing form preserves the most value, because the shape, strength and embodied energy of the component are retained.

Refurbishment or remanufacture preserves a large part of that value after repair or adaptation. Recycling recovers the material but destroys the form, and usually involves additional energy for reprocessing. Energy recovery and landfill sit at the bottom. Figure 3 ranks these options, and Figure 9 illustrates the same thinking for timber buildings, where the DfD principles address the upper loops of repair, maintenance, reconfiguration, repurposing, reuse and relocation.

A practical implication is that DfD cannot be judged only by whether a building can be demolished more neatly. Its real value depends on whether the recovered components have a destination. This is why the later sections of this paper emphasise inspection, grading, documentation and demand for recovered materials as much as the physical act of unbolting a connection.




Figure 3: Waste hierarchy applied to building components (schematic)

C. Terminology

Several related terms appear in the literature and are sometimes used interchangeably. *Design for Disassembly* and *Design for Deconstruction* both refer to planning for the orderly separation of building parts. *Design for Adaptability* focuses on enabling a building to change use or layout during its life without major reconstruction. *Reversible building* is used for a building in which assembly steps can be reversed so that elements can be changed, relocated or removed. *Design for Reuse* stresses the second life of recovered components. In practice these goals overlap, and international guidance, such as ISO 20887 [6], treats disassembly and adaptability together.

D. DfD, Adaptability and Durability

It is sometimes assumed that designing a building to be taken apart conflicts with designing it to last. The two goals are better understood as complementary. A building that lasts a long time, but cannot be adapted, is often demolished early because it no longer suits its users.

International Journal of Recent Development in Engineering and Technology
Website: www.ijrdet.com (ISSN 2347-6435 (Online) Volume 15, Issue 10, October 2026)

A building that can be adapted and repaired is more likely to remain in use, and each replacement of a short-life layer extends the life of the whole. DfD therefore supports durability at the level of the building even when individual components are replaced at the level of the layer.

This relationship has two consequences for design. First, long-life layers such as the primary structure should still be designed for durability, since their value is greatest when they remain in place for a long time. Second, short-life layers should be designed for easy replacement rather than for permanence, because trying to make them last as long as the structure often leads to heavy, bonded constructions that are difficult to repair. The art of DfD lies in matching the degree of reversibility to the expected life and role of each element.

IV. Principles Of Design For Disassembly

DfD requires the future removal of components to be considered alongside assembly, structural performance and everyday use. Each principle below is stated together with the reasoning that supports it.

- *Accessible connections* — Joints should remain reachable for inspection and removal, with sufficient clearance for appropriate tools. A fastener that is buried behind finishes, poured into concrete or surrounded by other members cannot realistically be released, however reversible it may be in principle.
- *Reversible fastening* — Bolts, screws and removable pins or dowels should be considered where suitable for the load and intended use. The key requirement is that the joint can be opened without cutting, burning or breaking the connected members.
- *Reduced dependence on permanent joints* — Adhesives, welds and wet joints may make separation destructive and should be limited where reversibility is required. This does not forbid their use; it asks the designer to use them deliberately and only where their advantages outweigh the loss of recoverability.
- *Material separation* — Different materials should be arranged so they can be separated rather than bonded into mixed assemblies. Composite panels, laminated finishes and bonded insulation often cannot be sorted after use, so their constituent materials are lost to recycling.
- *Simple and independent components* — A component should be removable without requiring the destruction or removal of many neighbouring elements. Independence limits the cascade of work that follows from a single repair or replacement.
- *Standardisation and reuse* — Standard dimensions and interfaces can improve the possibility of using components in another suitable location. A recovered element that fits a common module is far easier to place in a new building than a one-off custom unit.
- *Planned removal sequence* — The sequence of dismantling should be considered during design and documented for future teams. Load paths, temporary supports and stability during partial removal need to be understood in advance.
- *Component information* — Drawings and digital records can identify materials, locations, connections and properties. Information about what a building contains is as important to future recovery as the physical details of its joints.

Two further considerations are implicit in the seminar material and are worth stating explicitly. The first is *durability and safety*: a connection designed for easy release must still resist the loads, vibration, fire, moisture and misuse expected during service. The second is *proportionality*: not every component needs to be designed for disassembly to the same degree. Effort is best concentrated on elements that are valuable, that are likely to be replaced, or that are difficult to recover by other means.



Figure 4: Reversible buildings with independent layers

Figure 5 summarises how several of these principles can be combined in a simple decision sequence that a designer may follow for each element. The sequence asks first whether the element is likely to change, then whether its joint can be reached with standard tools, and finally whether the materials can be separated. Elements that are unlikely to change may use permanent joints, provided they are documented, so that the principle of proportionality is respected.

International Journal of Recent Development in Engineering and Technology
Website: www.ijrdet.com (ISSN 2347-6435 (Online) Volume 15, Issue 10, October 2026)




Figure 5: Conceptual decision sequence for choosing joints (schematic)

V. Reversible Connections and Construction Strategies

A. Types of Reversible Connections

Bolted connections. Common in steel and timber construction. Nuts and bolts can be removed to open the joint without cutting the connected members. Bolted joints are well understood by designers and contractors, can be inspected visually and can be re-tightened after relocation. Slotted or oversized holes may ease alignment but need to be detailed carefully to maintain strength and stiffness.

Screwed connections. Useful for lighter elements such as cladding, panels and fixtures that may need to be removed and refitted. Repeated removal can enlarge screw holes, particularly in softer materials, so the number of expected cycles and the use of inserts or replaceable fixings should be considered.

Doweled or pinned connections. Removable pins or dowels transfer load, particularly in timber systems, without permanently bonding the members. They are valued where a clean appearance or limited visible metalwork is desired, but accurate fabrication is important for the joint to transfer load as intended.

Cam-lock or click connections. Proprietary fittings allow quick connection and release in some modular and prefabricated systems. They can speed up assembly and disassembly, though dependence on a specific product raises questions about long-term availability of the fitting.

Dry-stacked or friction connections. Units rely on gravity and friction and can be lifted away in reverse order where the system and loads permit. They suit certain modular and masonry-type systems but require attention to lateral stability, tolerances and the effect of repeated loading.

Welding, structural adhesives and wet concrete joints are generally less suitable where repeated disassembly is a priority because they can create permanent bonds. The choice of connection must nevertheless be based on structural demands, safety, durability and the intended frequency of opening; reversibility alone is not sufficient. Figure 6 sketches the five reversible families, and Figure 7 places the main joint types along a qualitative reversibility spectrum. Table I summarises their comparative characteristics.




Figure 6: Schematic of common reversible connection types




Figure 7: Qualitative reversibility spectrum of joint types

TABLE I
Comparison of Common Connection Types

Connection	Reversibility	Typical Use	Key Concern
Bolted	High	Steel and timber frames	Hole tolerance; corrosion
Screwed	Medium to high	Cladding, panels, fixtures	Wear of holes on reuse
Doweled / pinned	High	Timber systems	Fabrication accuracy
Cam-lock / click	High	Modular systems	Product availability
Dry-stacked	High	Modular units, masonry	Lateral stability
Welded	Low	Permanent steelwork	Cutting needed to separate
Adhesive / wet joint	Very low	Monolithic concrete, laminates	Bonded, mixed material

International Journal of Recent Development in Engineering and Technology
Website: www.ijrdet.com (ISSN 2347-6435 (Online) Volume 15, Issue 10, October 2026)

B. Design Methods and Strategies

Modular design divides a building into units that can be added, removed or relocated. Standardisation allows components to fit common dimensions and interfaces, while prefabrication can improve control over the manufacture and assembly of components. A planned disassembly sequence helps make future removal systematic and safe. Material documentation, including drawings and digital records, supports identification and assessment of recovered components.

Modularity and grids. A coordinated dimensional grid ensures that slabs, wall panels, windows and finishes share compatible sizes. The Helsinki project discussed later used a 3M (300 mm) module for exactly this reason. A consistent grid also reduces off-cuts during construction, which is a benefit even before the building is ever disassembled. Figure 8 shows how wall, window and slab units can all be expressed as multiples of the same module.




Figure 8: Modular grid coordination on a 300 mm (3M) basis (illustrative dimensions)

Prefabrication. Factory production allows tighter tolerances, better quality control and the integration of reversible connection details that may be difficult to achieve on site. Prefabricated elements are naturally conceived as discrete units and are therefore well suited to later removal. Transport limits, crane capacity and site access nevertheless influence the size of units.

Layered separation of services. Distributing pipes and cables in accessible shafts, trays or raised floors, rather than embedding them within structural elements, allows services to be upgraded or replaced without disturbing the structure.

Design for the likely number of cycles. A connection used once at the end of life can be detailed differently from one expected to be opened frequently. Designers should consider the intended frequency and purpose of opening and choose the lightest solution that is adequate.




Figure 9: Circular solutions for timber buildings in the technosphere. DfD principles address the top right corner regarding repair, maintain, reconfigure, repurpose, reuse and relocate.

C. Material-Specific Considerations

Timber. Timber is well suited to mechanical connection and to prefabrication. Reversible timber connection systems have been reviewed in the literature [3], including dowel-type, bolted and proprietary systems. Repeated drilling and fastening can reduce the usable section of a member, so connection positions should be planned to allow re-use without weakening. Protection from moisture is essential to maintain the condition of recovered timber.

Steel. Steel members are strong, easily bolted and widely reused in practice when connections are accessible. Bolted rather than welded joints, standard section sizes and records of steel grade greatly increase the chance of reuse. Corrosion, fatigue history and unknown grade can limit the reuse of recovered steel unless properly assessed.

Concrete. Cast-in-place concrete is intrinsically difficult to disassemble. Precast concrete with dry mechanical connections, rather than grouted or cast-in joints, provides a more promising route to recovery. The Helsinki case discussed below retained a concrete frame while modifying the surrounding systems to make them detachable, showing that DfD can also be applied to buildings with concrete structures.

Masonry and cladding. Mortars based on strong cement bind units together so that they cannot be separated cleanly. Weaker, lime-based mortars or dry-stacked arrangements permit recovery of units. Lightweight cladding fixed with accessible fasteners can be removed and replaced independently of the main structure.

Finishes and insulation. Finishes bonded directly to substrates often make both materials unrecoverable. Mechanically fixed finishes and loose-laid or mechanically held insulation are more compatible with the goals of DfD.

International Journal of Recent Development in Engineering and Technology
Website: www.ijrdet.com (ISSN 2347-6435 (Online) Volume 15, Issue 10, October 2026)

D. Structural, Durability and Fire Considerations

A reversible joint is only acceptable if it performs at least as reliably as a permanent one during the life of the building. Structural designers must therefore verify strength, stiffness and ductility in the normal way, and must also consider the effects of repeated assembly. Bolted and dowelled joints can exhibit slip, which affects deflection and vibration behaviour, and tolerances in holes and fittings must be controlled so that load is shared as intended among fasteners.

Durability is a second concern. Exposed fasteners may corrode, and corrosion not only weakens the joint but can also make later removal difficult or impossible. Protective coatings, suitable material selection and detailing that keeps water away from the joint all support both durability and later reversibility. Where joints are likely to be opened more than once, wear-resistant fixings and replaceable inserts help preserve the recovered components.

Fire performance must be addressed because exposed connectors and demountable assemblies may behave differently from monolithic construction. Fire protection layers should themselves be designed so that they can be removed and replaced without damaging the elements they protect, and compartmentation should be maintained wherever panels or service openings are made accessible. Acoustic performance and airtightness similarly depend on the quality of joints between demountable elements and require seals that remain effective after repeated opening.

Finally, the designer must consider construction and deconstruction tolerances. Components assembled with tight tolerances may be difficult to separate if materials swell, corrode or settle, while overly loose tolerances may reduce performance. Mock-ups and trial assemblies, particularly for new details, are useful ways to check that a reversible joint can be assembled, loaded and opened as planned.

E. Interfaces between Systems

Many of the practical difficulties in reversible construction occur at interfaces, where one system meets another. A façade panel meets the structure, a partition meets a ceiling, a pipe passes through a wall. Interfaces must resolve several requirements at the same time, including load transfer, movement, weather protection, fire separation and acoustic performance, and they must remain workable when opened. Standard interface details, tested and reused across projects, reduce risk and cost and make it easier for contractors to learn and repeat the work.

Interfaces are also where tolerances accumulate. Differences between the dimensions of fabricated components and those of the supporting structure must be absorbed by adjustable fixings, slotted holes or compressible seals, rather than by cutting, packing or sealing with permanent materials. Allowing for adjustment at the interface keeps the system reversible and also eases original construction.

VI. Building Layers And Service Life

Buildings contain layers that change at different rates. The site and primary structure generally have longer service lives than services, partitions, furniture and finishes. Façades occupy an intermediate position. This view of a building as a set of layers with different rates of change is widely attributed to Stewart Brand's work on how buildings adapt over time [10]. It remains a useful basis for DfD because it links the physical arrangement of a building with the time scale of its changes.

Designing these layers as separate systems allows short-life elements to be replaced without unnecessary disturbance to the long-life structure. This separation is especially important for electrical and plumbing services, which may need upgrading several times during a building's life (Table II). In a building in which layers are entangled, a minor upgrade to a short-life layer can force invasive work on long-life layers, increasing cost, waste and disruption. Figure 10 gives a qualitative picture of these differing rates of change.




Figure 10: Building layers and indicative relative service life (qualitative)

International Journal of Recent Development in Engineering and Technology
Website: www.ijrdet.com (ISSN 2347-6435 (Online) Volume 15, Issue 10, October 2026)

TABLE II
BUILDING LAYERS AND INDICATIVE SERVICE LIFE

Building Layer	Examples	Indicative Service Life
Site	Land and surroundings	Very long
Structure	Columns, beams and slabs	Long
Skin/façade	External walls and windows	Medium to long
Services	Electrical systems, plumbing and HVAC	Medium
Space plan	Internal partitions	Short to medium
Interior/stuff	Furniture and finishes	Short

Table III relates each layer to practical DfD strategies. The recommendations are general and need to be adapted to the project, but they show how the layered view can be turned into design decisions.

TABLE III
DFD STRATEGIES BY BUILDING LAYER

Layer	Suggested DfD Strategy
Structure	Dry or bolted joints; standard member sizes; precast or timber systems; accessible connections
Skin/façade	Mechanically fixed panels; independent support; replaceable glazing units
Services	Accessible shafts and trays; no embedding in structure; labelled routes
Space plan	Demountable partitions; non-load-bearing layout; reusable panels
Interior/stuff	Loose-laid or mechanically fixed finishes; standard units; easy replacement

Layer independence also allows maintenance to proceed without halting the use of the whole building. Where services are routed through accessible shafts, a faulty pipe can be repaired without breaking into slabs. Where façade panels are fixed independently of the structure, a damaged panel can be replaced from the outside without interfering with interior spaces. Figure 11 illustrates the difference between embedded and accessible service routes.




Figure 11: Embedded services versus an accessible service shaft (schematic)

VII. DISASSEMBLY PROCESS

A planned disassembly process is generally the reverse of construction, but it requires assessment and safety planning rather than simply reversing the assembly steps. The building may have been altered since it was constructed, materials may have aged, and the load paths in a partly dismantled structure differ from those of the completed building. The sequence described in the supplied materials consists of the following stages:

1. *Building assessment:* Survey the building condition, materials and any hazardous substances before work begins. Surveys should identify the presence of materials that require special handling so that they are not released or mixed with recoverable materials.
2. *Component identification:* Map components, connections and load paths using available drawings or material records. Where records do not exist, physical investigation may be required.
3. *Disassembly planning:* Set the removal sequence and provide the required safety measures and temporary support. The plan should state lifting methods, access, storage and transport.
4. *Accessing connections:* Reach fixings and open them using tools appropriate to the fastener type. Corroded or seized fixings may require careful treatment to avoid damaging the component.
5. *Component removal:* Lift or unbolt elements as complete units and support them to prevent dropping, bending or cracking.
6. *Material sorting:* Separate components by material and condition into reusable, repairable and recyclable groups.

International Journal of Recent Development in Engineering and Technology
Website: www.ijrdet.com (ISSN 2347-6435 (Online) Volume 15, Issue 10, October 2026)

7. *Inspection:* Assess damage, strength and suitability for the proposed second use. Testing or grading may be needed before structural reuse, and the requirements of the new application govern acceptance.
8. *Reuse, refurbishment or recycling:* Reuse approved components, refurbish recoverable parts and recycle remaining materials where possible.




Figure 12: Disassembly process

The three groupings shown in Fig. 12, preparation, disassembly and recovery, emphasise that the work does not start at the first bolt and does not end at the last lift. Preparation determines whether the work can be done safely and efficiently, and recovery determines whether the effort leads to real reuse. Table IV links the stages with the main information or action that each requires.

TABLE IV
DISASSEMBLY STAGES AND KEY REQUIREMENTS

Phase	Stage	Key Requirement
Preparation	Assessment	Condition and hazard survey
Preparation	Identification	Drawings, records, load paths
Preparation	Planning	Sequence, supports, safety
Disassembly	Access	Suitable tools and clearance
Disassembly	Removal	Lifting and support equipment
Disassembly	Sorting	Separate storage areas
Recovery	Inspection	Grading and testing
Recovery	Reuse / recycle	Market or second-use project

Safety is central to all stages. A structure being dismantled passes through intermediate states for which it was never designed, so temporary bracing, controlled sequencing and competent supervision are essential. DfD helps by making the sequence explicit and the connections accessible, but it does not remove the need for professional engineering judgement during the work itself.

A. Site Management and Safety

Site management for disassembly differs from that for demolition. Because components are to be recovered intact, lifting equipment, temporary storage and protection from weather must be arranged before work begins. Components should be labelled as they are removed so that their original location and orientation are known, which helps when elements are matched to their records or reassembled elsewhere. Waste streams should be kept separate at source, since mixing recoverable materials with contaminated or damaged debris reduces the value of both.

Workers need clear instructions on the sequence and on any hazards, including stored energy in tensioned elements, unstable partially dismantled frames and falling objects. Method statements should be prepared by competent persons and updated if the actual condition of the building differs from the records. Hazardous materials identified in the survey must be removed under appropriate controls and kept apart from materials intended for reuse.

B. Grading and Reuse Pathways

Recovered components may follow several routes. Elements in good condition with known properties can be reused directly, either on the same site or elsewhere. Elements with minor damage can be refurbished, for example by replacing fixings, refinishing surfaces or trimming to a smaller size. Elements that cannot be reused in their present form can be reprocessed, for example by recycling timber into panel products or steel into new sections. A clear grading scheme, in which each recovered element is placed in a defined category based on inspection, helps buyers and designers decide whether an element suits a particular application.

Reuse is easier where there is a place to hold and exchange recovered components. Storage yards, exchange platforms and specialist dealers all reduce the time between recovery and reuse, and thereby reduce the cost and deterioration associated with holding stock. Without such channels, even a well-planned disassembly may end in disposal because no buyer is available when the components are released.

International Journal of Recent Development in Engineering and Technology
Website: www.ijrdet.com (ISSN 2347-6435 (Online) Volume 15, Issue 10, October 2026)

VIII. Documentation, Material Passports and Digital Tools

Physical reversibility is of limited use unless the people who eventually dismantle the building know what it contains. Over decades, drawings are lost, owners change and details are forgotten. DfD therefore places great importance on documentation, which should record the materials used, their quantities and locations, the type and position of connections, and the intended disassembly sequence.

A *material passport* is a structured record that identifies the components and materials in a building and describes their properties, origins and recovery potential. Its purpose is to give recovered materials an identity so that future designers and contractors can assess them with confidence. Passports may include information on dimensions, material grade, finishes, treatments, hazardous content and maintenance history. Figure 13 summarises the main groups of information that a passport may hold.




Figure 13: Typical information groups in a material passport (schematic)

Digital tools such as building information modelling (BIM) allow the geometry and attributes of components to be stored in a single model that can be updated during the life of the building. Quick-response codes or other tags attached to components can link the physical element to its digital record. Such tools can also support planning of the disassembly sequence by identifying which elements depend on others.

Metrics for assessing the disassembly potential of building components are an active research topic [5]. Systematic reviews of built structures designed for disassembly [4] indicate the range of approaches taken in practice. These sources suggest that a common language for describing and scoring reversibility will help clients, designers and regulators compare options and set goals. The existence of a standard such as ISO 20887 [6] provides a framework of principles, requirements and guidance in this area.

IX. Stakeholder Roles and Lifecycle Integration

DfD cannot be achieved by designers alone. Decisions that affect future disassembly are made by clients when they set briefs and budgets, by designers when they select systems and details, by manufacturers when they produce components, by contractors when they assemble the building, and by owners and facility managers throughout use. Each of these parties can either support or undermine reversibility, and early agreement on shared goals is therefore essential.

The client has the greatest influence at the start because the brief determines whether adaptability and recovery are treated as requirements or as optional extras. Architects can reduce future constraints through layered planning, simple geometry and standard grids. Structural and services engineers translate these intentions into connection details, load paths and routes for services. Manufacturers contribute by supplying components with standard interfaces and by providing information on materials and treatments. Contractors must follow the intended assembly sequence and record any changes, while facility managers keep records current during use. Table V summarises these roles.

TABLE V
Stakeholder Roles in Design for Disassembly

Stakeholder	Main Contribution
Client / owner	Sets reversibility and adaptability goals; funds documentation
Architect	Layered planning; modular grid; simple geometry
Structural engineer	Reversible joints; load paths; temporary stability
Services engineer	Accessible routes; independent systems
Manufacturer	Standard interfaces; product and material data
Contractor	Follows sequence; records as-built changes
Facility manager	Maintains records; plans component replacement
Deconstruction team	Executes sequence; inspects and sorts components

Lifecycle integration means linking these roles over time. At the design stage the intended disassembly sequence is drawn up. During construction the as-built information is verified and the passport is completed. During use, maintenance, repair and alterations are added to the record. At the end of life the record is the starting point for the survey described in Section VII.

International Journal of Recent Development in Engineering and Technology
Website: www.ijrdet.com (ISSN 2347-6435 (Online) Volume 15, Issue 10, October 2026)

When any link in this chain breaks, for example when records are lost at a change of ownership, the physical reversibility of the building loses much of its practical value.

Contractual arrangements also matter. Procurement routes that separate design from construction and operation can make it difficult to reward measures whose benefits arrive decades later. Approaches that give the owner or a long-term operator an interest in the residual value of components, or that assign responsibility for recording information, are more likely to support DfD in practice.

X. Applications, Benefits, Challenges And Limitations

A. Applications

DfD can be applied to residential buildings, offices and shops that may require future modification, educational buildings with changing space requirements, modular and prefabricated buildings, temporary structures, timber construction and building renovation. At the end of a building's service life, DfD can also support recovery of components for reuse or recycling.

Commercial buildings are a particularly relevant application because tenants and layouts change often. Offices designed with demountable partitions, raised floors and accessible services can be reconfigured with limited waste. Educational buildings face varying class sizes and teaching methods, so flexible, modular spaces help them to stay useful. Temporary structures such as exhibition pavilions, event buildings and site accommodation are by definition meant to be taken apart, and so DfD represents their natural design logic. Figure 14 shows an office building in the Netherlands associated with demountable construction thinking.



Figure 14: Park 20|20, office building, Netherlands

B. Potential Benefits

The benefits claimed for DfD fall into environmental, economic and social groups. *Environmentally*, DfD may reduce the volume of demolition waste, lower demand for virgin materials and retain embodied energy and carbon in reused components. Research on time-resolved life-cycle assessment [1] indicates that the benefits of DfD depend on assumptions about future reuse, which means its environmental advantages are not automatic and should be evaluated for each case. Table VI contrasts conventional and DfD-oriented practice in qualitative terms. *Economically*, components that can be recovered retain residual value, and adaptable buildings may avoid costly reconstruction when use changes. *Socially*, adaptable buildings can respond to changing community needs, and recovery and refurbishment activities can create skilled work.

TABLE VI
Conventional Construction versus DfD (Qualitative)

Aspect	Conventional	DfD-oriented
Joints	Often permanent	Reversible where valuable
Layers	Entangled	Independent
Services	Often embedded	Accessible routes
Records	Limited, often lost	Passport and as-built data
Renovation	Invasive, wasteful	Targeted replacement
End of life	Demolition	Sequenced disassembly
Initial effort	Lower	Higher design effort

C. Challenges and Limitations

Implementation may involve higher initial costs for special connectors, design development and documentation. Connection details require careful engineering, and trained workers may be needed for installation and removal. Standard or reusable components may not always be available. In addition, a component recovered from one building may be damaged, fail to meet the requirements of a new use or have no immediate market. Future user needs and technologies are difficult to predict, so complete reversibility cannot be assumed to be suitable for every building. Coordination among architects, engineers, contractors and suppliers is therefore important. Comparisons of the cost of deconstruction and demolition for a prefabricated concrete building designed for disassembly [8] show that such economic questions are being examined in the literature, and Table VII groups the main challenges and suggests possible responses.

International Journal of Recent Development in Engineering and Technology
Website: www.ijrdet.com (ISSN 2347-6435 (Online) Volume 15, Issue 10, October 2026)

TABLE VII
MAIN CHALLENGES AND POSSIBLE RESPONSES

Challenge	Possible Response
Higher initial cost	Assess whole-life cost; focus effort on valuable, frequently replaced elements
Complex connection design	Use proven bolted, doweled or modular details; early engineering input
Skilled labour	Training; clear assembly and removal instructions
Lack of standard components	Adopt modular grids; coordinate with suppliers
Damaged or untested recovered parts	Inspection, grading and testing protocols
No market for recovered components	Plan second use; storage and exchange platforms
Uncertain future needs	Adaptable layouts; independent layers
Fragmented responsibility	Early collaboration; defined roles for disassembly

Regulation and liability also deserve mention. Building codes and product standards are usually written for new materials, so the structural reuse of recovered components may require additional testing and may raise questions about responsibility if a reused element performs unexpectedly. Insurers, clients and authorities may be unfamiliar with reused components and may ask for evidence of their quality. Clear documentation, testing and agreed grading procedures can help to address these concerns.

There is also a risk of over-designing. If every joint in a building were designed for repeated disassembly regardless of its purpose, the building could become more expensive and more complex than needed. The aim should be to identify where reversibility delivers real value and to apply it there.

XI. Standards, Policy And Regional Context

A. Standards and Guidance

International guidance on design for disassembly and adaptability is provided by ISO 20887 [6], which sets out principles, requirements and guidance for buildings and civil engineering works. Earlier guidance and research on design for disassembly, including practical guides for the built environment [13] and theses on transformable building structures [12], established many of the concepts now used in practice, such as separating building layers, using mechanical connections and documenting components. Design guides prepared for the construction industry [14] also summarise themes and principles that remain relevant.

B. Policy Instruments

Policy can encourage DfD by changing the economics and obligations of construction. Table VIII lists instruments that are commonly discussed in the literature on circular construction. Their effectiveness depends on local conditions and they are listed here as options for consideration rather than as recommendations for any particular jurisdiction.

TABLE VIII
POLICY INSTRUMENTS SUPPORTING REVERSIBLE CONSTRUCTION

Instrument	Intended Effect
Pre-demolition audits	Identify recoverable materials before demolition
Reuse targets	Create demand for recovered components
Material passport requirements	Ensure information survives ownership changes
Reuse-friendly codes and testing	Allow safe structural reuse with evidence
Green procurement criteria	Reward adaptable, disassemblable design
Landfill charges	Make disposal less attractive than recovery

C. Relevance to India and Kerala

India's construction sector is large and growing, and Kerala has its own pressures, including high land costs, a humid climate that affects durability and a tradition of both masonry and timber building. In such conditions, steel and timber systems with bolted connections, precast and prefabricated elements, and lightweight infill panels offer realistic starting points for reversible construction. Temporary and semi-permanent buildings used for cultural events, markets and site accommodation are common and are natural candidates for early adoption, as the Container pavilion illustrates.

Practical obstacles include limited availability of tested reused components, limited familiarity with demountable details among contractors, and the absence of widely used procedures for grading recovered structural members. Monsoon conditions place particular importance on protecting joints from water and on storing recovered materials in dry conditions. Local research on material flows, costs and suitable details would help identify where DfD can deliver the greatest benefit.

International Journal of Recent Development in Engineering and Technology
Website: www.ijrdet.com (ISSN 2347-6435 (Online) Volume 15, Issue 10, October 2026)

XII. Implementation Roadmap And Design Checklist

A. Implementation Roadmap

The preceding sections suggest that organisations can move towards DfD in stages. Table IX sets out a conceptual roadmap from preparation through to learning from completed projects. It is intended as a planning aid and has not been tested as a formal method.

TABLE IX
Conceptual Roadmap for Adopting DfD

Stage	Typical Actions
1. Set goals	Define reversibility and reuse aims in the brief
2. Plan layers	Separate structure, skin, services and space plan
3. Choose systems	Select modular, prefabricated or timber/steel frames
4. Detail joints	Specify accessible, reversible connections
5. Document	Create drawings, passport and removal sequence
6. Build and verify	Record as-built data; check connection access
7. Operate	Maintain records; replace short-life layers
8. Recover	Survey, dismantle, grade and reuse components

B. Design Checklist

To help bring together the principles discussed above, a simple checklist is proposed in Table X for use at design stages. It is a conceptual aid compiled from the principles in this paper; it has not been tested or calibrated and does not generate a numerical score.

TABLE X
Conceptual DfD Checklist for Design Stages

Design Stage	Question to Ask
Concept	Which elements are likely to change, and how often?
Concept	Are layers (structure, skin, services, space plan) separate?
Structure	Are joints bolted, doweled or dry rather than welded or cast-in?
Structure	Is there clear access to every connection?
Envelope	Can façade panels be removed without disturbing the structure?
Services	Are services in accessible shafts rather than embedded?
Materials	Can different materials be separated without damage?
Dimensions	Does the design follow a standard module?
Documentation	Are materials, connections and sequence recorded?
End of life	Is there an intended route for reuse or recycling?

Used at successive design stages, the checklist can guide discussions among the design team, the client and contractors. A "no" answer does not necessarily indicate a design fault, but it signals a point where the team should consider whether a different detail would improve recoverability at acceptable cost.

XIII. Case Studies

A. Helsinki Apartment Block, Finland

The supplied seminar materials describe a DfD redesign of an existing Helsinki apartment block associated with Joensuu and Saari [2]. The spatial layout was largely retained while component dimensions and connections were reconsidered. A 3M (300 mm) modular grid was used for slabs and wall panels to support standardised dimensions. The heavy masonry façade was replaced with a lightweight timber façade, and prefabricated balconies were attached without cutting into the load-bearing concrete frame. Separate side supports allowed balconies to carry their own loads and be unbolted as individual units. Pipes and cables were centralised in service shafts rather than placed within hollow-core slabs, allowing services to be upgraded with less disturbance to the slabs.

According to the supplied presentation and report, the life-cycle analysis found that the DfD concrete frame had a smaller carbon footprint than a same-size conventionally built timber-framed block when standardised components were reused. This result is reported as presented in the source material; the underlying analysis and assumptions were not independently examined for this paper. The case illustrates the potential value of modular sizing, independent components, accessible connections and separation of building services. Public reporting on the work [7] also describes the approach as promising for improving the economic and environmental performance of buildings.

The Helsinki project is instructive because it did not rely on a new structural system. Instead it showed that a conventional concrete frame can be combined with detachable envelope elements, independent balconies and accessible services. The design choices in this case map directly onto the principles of Section IV: standardisation through the 3M grid, independence through the separate balcony supports, accessibility through service shafts, and material separation through a lightweight façade fixed independently of the frame.

International Journal of Recent Development in Engineering and Technology
Website: www.ijrdet.com (ISSN 2347-6435 (Online) Volume 15, Issue 10, October 2026)



Figure 15: Helsinki apartment block redesigned for disassembly

Figure 16 sketches the balcony principle in simplified form: the balcony is bolted to the frame and rests on its own side support, so that it can be unbolted and lifted away as a unit without cutting into the concrete.




Figure 16: Independent, bolted balcony support (schematic, simplified)

B. The Container, Kochi-Muziris Biennale 2023

The Container was described in the seminar materials as a temporary cultural pavilion in Fort Kochi, created for the 2023 Kochi-Muziris Biennale and intended for relocation. Its steel frame supported wire mesh and a geogrid textile roof. The roof build-up used brick powder, coir, cement and mud held by brick bunds. Gabion-like wall panels incorporated construction debris and waste granite, with coir and fishing-net elements contributing to the enclosure.

The pavilion did not use conventional concrete footings; its steel box sat on the ground and could be dismantled, transported by road and reassembled elsewhere. The project demonstrates how temporary architecture can treat recovered materials as resources and how accessible layers and recoverable components can support a future second use.

It also shows that DfD principles can be relevant to small, temporary structures as well as larger residential buildings.

The Container is of particular interest to a Kerala readership because it uses locally familiar materials such as coir and brick together with waste streams from the region, and because it was built for a public cultural event with a defined duration. In this setting the short intended life of the structure makes disassembly an explicit requirement from the outset, rather than a distant concern. The use of a self-supporting steel box that sits on the ground without conventional footings removes one of the most difficult elements to recover, the buried foundation, and makes the site easier to return to its earlier condition.



Figure 17(a): The Container, Fort Kochi, 2023



Figure 17(b): Construction detail of the wall panels. Original project images: Share Your Green Design [9]

C. Comparison of the Two Cases

TABLE XI
COMPARISON OF THE TWO CASE STUDIES

Aspect	Helsinki Block	The Container
Building type	Residential apartment block	Temporary cultural pavilion
Approach	Redesign of existing block for DfD	Designed for relocation
Structure	Concrete frame retained	Steel frame box
Envelope	Lightweight timber façade	Wire mesh, geogrid, gabion-type panels
Key DfD features	3M grid; unbolted balconies; service shafts	No footings; transportable; recovered materials
Main lesson	DfD can suit housing and concrete frames	DfD can suit temporary, low-cost work

International Journal of Recent Development in Engineering and Technology
Website: www.ijrdet.com (ISSN 2347-6435 (Online) Volume 15, Issue 10, October 2026)

Despite differences of scale, material and purpose, the two cases share several features. Both treat the building as a set of separable systems rather than as a monolith. Both avoid or limit connections that cannot be reversed, and both consider the later life of the components at the design stage.

XIV. Discussion And Future Scope

The two case studies illustrate different scales of application. The Helsinki example focuses on a residential building, where modular dimensions, detachable balconies and separate service routes support component replacement and recovery. The Container focuses on temporary architecture and the use of recovered materials in a structure intended to be moved. Both examples emphasise that decisions made at the design stage influence how much value can be retained when a building is changed or dismantled.

A broader reading of the material suggests several themes. First, DfD works best when it is treated as a design goal from the start. Attempts to add reversibility late in design are less effective because the layout, grid and structural system are already fixed. Second, reversibility is a spectrum rather than a binary property, and designers must decide how far to pursue it for each component. Third, the technical details of connections cannot be separated from the organisational and economic conditions needed for reuse, including storage, testing and markets for recovered products.

Further development may include improved reversible connectors, wider use of modular and prefabricated systems, digital building records and material passports that identify components and their properties. Robotic disassembly may offer future opportunities for safer and more efficient component removal. Better material recovery practices and design standards could also support wider adoption. Policy instruments, such as requirements for pre-demolition audits, targets for reuse or incentives for recovered components, may also encourage the sector to move in this direction. These developments will be most useful when combined with reliable documentation, appropriate structural design and practical pathways for storing, testing and reusing recovered components.

For countries such as India, where construction activity is growing rapidly, the potential relevance of DfD is considerable. Prefabrication and modular systems are increasingly used, and temporary and semi-permanent structures are common. However, the availability of trained labour, quality assurance for reused products and local standards will influence how far the approach can be adopted. Research into local material flows, costs and suitable connection details would help to establish where DfD offers the greatest benefit.

To illustrate the benefit of layered design, consider a conceptual example of an office building in which a tenant requires a new partition layout and an upgrade of cabling. In a building with entangled layers, partitions may be built up to the slab soffit with wet finishes, and cables may be embedded in floor screeds. Altering the layout then requires breaking partitions and floors, creating dust, debris and mixed waste, and possibly affecting adjacent areas. In a building designed with demountable partitions and accessible floor voids, the same change can be carried out by unfastening panels and relocating them, and by lifting access panels to reach cables. The existing materials remain largely intact and can be used again. Figure 18 shows this contrast over the life of a building in schematic form.




Figure 18: Replacement events over building life in entangled and independent layer arrangements (schematic)

The example also shows why DfD is as much about operation as about demolition. Most of the benefit in a typical building arises not at the end of life but during the many modifications that occur before it, each of which can be easier, cleaner and cheaper if the building was planned for change. This suggests that the case for DfD should be built around adaptability and maintenance savings as well as end-of-life material recovery, and that evaluation methods should consider the whole life of the building rather than a single end-of-life event.

A further point concerns the quality of information. Many of the difficulties reported in reuse practice relate to uncertainty about the properties of components rather than to the difficulty of removing them. If grade, age, treatment and loading history are unknown, designers must apply cautious assumptions or carry out additional testing, which raises cost. Reliable records created at the time of construction therefore have a direct effect on the economic prospects of reuse, and justify the effort of preparing passports even where the end of the building's life is distant.

International Journal of Recent Development in Engineering and Technology
Website: www.ijrdet.com (ISSN 2347-6435 (Online) Volume 15, Issue 10, October 2026)

Several limitations of this review should also be acknowledged. It relies on supplied seminar materials and on published sources that were not independently checked, and it draws on two case studies of very different scale. The qualitative tables, figures and checklists included here are conceptual aids and do not represent measured performance. Readers who wish to apply the ideas should consult the primary sources, applicable standards and project-specific engineering advice.

Areas for future research include quantitative studies of the cost and carbon impacts of DfD in a variety of building types and climates, long-term monitoring of the performance of reversible connections, development of testing and grading methods for reused structural components, and investigation of how material passports can be integrated with existing design and procurement processes.

XV. Conclusion

Design for Disassembly shifts attention from a building's initial assembly to its full life cycle, including adaptation, repair, component recovery and end-of-life treatment. Accessible reversible connections, standardised components, prefabrication, independent building layers and a planned removal sequence can make disassembly more practical and reduce avoidable damage. The Helsinki apartment block and The Container pavilion provide examples of how these ideas can be applied in residential and temporary construction.

However, DfD is not automatic: initial planning, suitable connections, skilled labour, component records and demand for recovered materials all affect its success. Its benefits are strongest where reversibility is applied with judgement to the elements that matter most, and where the surrounding system of documentation, inspection and reuse is in place. Integrating disassembly considerations at the design stage can help buildings contribute to a more circular use of construction materials.

Several practical messages follow from this review. Designers should identify early which elements are most likely to change and concentrate reversible detailing there. Engineers should treat reversible joints with the same rigour as permanent ones, paying attention to durability, fire, tolerance and repeated use. Owners and managers should keep records current, since information is as important to future recovery as the joints themselves. Policy makers and industry bodies can support adoption through standards, audits and channels for the exchange and certification of recovered components. Finally, researchers should continue to gather measured data on cost, carbon and performance so that the claims made for DfD can be tested across a wider range of buildings, materials and climates.

Appendix: Glossary of Terms

Adaptability: The capacity of a building to be changed in layout or use during its life with limited work.

Circular economy: An economic model that keeps products and materials in use for as long as practicable.

Deconstruction: The careful, sequenced dismantling of a building to recover components and materials.

Design for Disassembly (DfD): Design that plans for the future separation of components with minimal damage.

Material passport: A record identifying the materials and components in a building and their properties.

Modular grid: A dimensional framework, such as 3M (300 mm), to which components are coordinated.

Prefabrication: Manufacture of building elements off site before assembly.

Reversible connection: A joint that can be opened without damaging the connected members.

Service life: The period over which a component or layer performs its function before replacement.

Acknowledgment

The authors thank the Department of Civil Engineering, Ahalia School of Engineering and Technology, for supporting the seminar work on which this paper is based.

REFERENCES

[1] Abu-Ghaida, H., Hollberg, A., Ritzen, M., Wohler, A., & Lizin, S. 2025. Assessing the environmental benefits of design for disassembly in buildings with a time-resolved prospective LCA approach. The International Journal of Life Cycle Assessment, 30, 1913–1929.

[2] Joensuu, T., & Saari, A. 2026. Design-for-Disassembly principles for apartment blocks—Experimental design in a Finnish housing project. Journal of Cleaner Production, 557, 148180.

[3] Ottenhaus, L. M., Yan, Z., Brander, R., Leardini, P., Fink, G., & Jockwer, R. 2023. Design for adaptability, disassembly and reuse—A review of reversible timber connection systems. Construction and Building Materials, 400, 132823.

[4] Design for Disassembly: A systematic scoping review and analysis of built structures designed for disassembly. 2024. Sustainable Production and Consumption, 48, 377–395.

[5] Building & Cities. Paper on metrics for assessing building component disassembly. DOI: 10.5334/bc.556.

[6] International Organization for Standardization. 2020. ISO 20887:2020: Sustainability in buildings and civil engineering works—Design for disassembly and adaptability—Principles, requirements and guidance.

[7] Tampere University. 2026. The Design for Disassembly approach holds promise for enhancing the economic and environmental performance of buildings. Tampere University News.

[8] Deconstruction of a prefabricated concrete building designed for disassembly—Cost comparison of deconstruction and demolition. 2025. IOP Conference Series. DOI: 10.1088/2634-4505/adcd27.

[9] Share Your Green Design. The Container (for Kochi-Muziris Biennale 2023).

[10] Brand, S. 1994. How Buildings Learn: What Happens After They're Built. Viking, New York.

[11] Ellen MacArthur Foundation. 2015. Towards a Circular Economy: Business Rationale for an Accelerated Transition.

[12] Durmisevic, E. 2006. Transformable Building Structures: Design for Disassembly as a Way to Introduce Sustainable Engineering to Building Design and Construction. Doctoral thesis, Delft University of Technology.

[13] Guy, B., & Ciarimboli, N. 2008. Design for Disassembly in the Built Environment: A Guide to Closed-Loop Design and Building.

[14] Crowther, P. 2005. Design for disassembly—themes and principles. BEDP Environment Design Guide.